

ライフサイクルコスト

パークハウスつくば研究学園 けやきレジデンス		工期 (年)	数量	単位	築年																															計 (千円)	備考
工事名称	修繕工事内容				会計年度	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023	2024	2025	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	2036	2037	2038	2039	2040		
1	仮設工事																																				
	足場		38443	m ²									73,100																						146,200		
	共通仮設		1	式									3,000																						6,000		
2	防水工事																																				
	屋根		3177	m ²									30,200																							77,800	
	庇・天端		8585	m ²									64,400																							128,800	
	バルコニー		6808	m ²									19,500																							84,200	
	テラス		614	m ²									1,300																							2,600	
	ゴミ置場床		227	m ²									1,800																							3,600	
	開放廊下		7960	m ²									22,700																							98,400	
	外部階段		1268	m ²									12,100																							15,800	
3	シーリング工事																																				
	目地		26597	m									37,300																							74,600	
	タイル目地		7306	m									8,800																							17,600	
	建具廻り		33588	m									37,000																							74,000	
4	下地補修工事																																				
	塗装仕上部		61126	m ²									18,400																							36,800	
	塗装面下地補修工事		6113	m ²									36,700																							73,400	
	タイル面補修工事		416	m ²									4,200																							8,400	
5	壁改修工事																																				
	壁 塗装仕上部		46998	m ²									112,800																							225,600	
	天井塗装仕上部		14128	m ²									24,100																							48,200	
	タイル仕上部		8325	m ²									7,500																							15,000	
6	鉄部塗装工事																																				
	各所鋼製箇所		454	戸									27,300																							136,500	
7	内装工事																																				
	床 塩ビシート		645	m ²																																6,200	
	床 フローリング等		456	m ²																																11,400	
	内部 壁天井塗装仕上部		4357	m ²																																10,500	
	集合郵便受		454	戸																																11,400	
	宅配ボックス		1	式																																2,600	
	開口部		1	式																																0	2044年度 22,700(千円)
	オートドア		1	式																															20,800		
8	外構工事																																				
	タイル貼舗装		61	m ²																																1,600	
	フェンス		213	m																																2,700	
9	給水設備工事																																				
	給水管		454	戸																																113,500	113,500
	ポンプ		6	組																																46,700	149,600
	減圧弁		454	戸																																4,600	9,200
	受水槽		5	基																																42,400	42,400
10	排水設備工事																																				
	排水管		454	戸																																136,200	136,200
	ポンプ		10	組																																3,800	15,200
11	ディスプレイ設置工事																																				
	ポンプ類		1	式																																500	3,000
	ブローヤ		1	式																																500	3,900
	フロートスイッチ		1	式																																200	2,000
	制御盤		1	式																																300	600
12	冷暖房設備工事																																				
	エアコン		12	組																																17,900	35,800
	全熱交換機器		7	台																																3,800	7,600
	換気扇		54	台																																17,400	34,800
13	電気設備工事																																				
	照明器具		2373	台																																35,600	71,200

